KADUR DIVISION.

ADVERTISEMENT.

The 7th October 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 30th October 1888, for improving and bridging the Banavar-Sakrepatna Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of Work.	Per.	Quantity.	Rate.
Earthwork excavation	C. Yd.	3,396	
Do gravelly soil	do	294	
Do excavation	do	1,430	
Rough square stone from the stream in mortar	C. ft.	4,839	
Burnt stone in mortar	do	46,089	
Archwork including cutting	do	5,893	
Burnt stone slabs	Sq. Ft.	1,473	
Cornice work	R. Ft.	50·92	
Guard stones	No.	8	
Clearing bed and baling water	Lp. sum Rs.	..	
Turfing slopes	do	..	
Approaches including earth from excavation	do	..	
Metalling including consolidation	C. Yd.	370	
Gravelling do	do	62	
Collection of gravel	do	894	
Carting do half-mile lead	do	894	
Picking road surface	Sqr.	7,150	
Spreading and consolidation of gravel	C. Yd.	894	

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes as earnest money, and be superscribed "Tender for improving and bridging the Banavar-Sakrepatna Road," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

D. SITARAMA RAO,
Executive Engineer.

MYSORE DIVISION.

ADVERTISEMENTS.

The 6th October 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 23rd October 1888, for restoring Mayappanahalli Tank, Mandya Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.